



Sai Wan Ho Civic Centre – Cultural Activities Hall

Basic Technical Information

V. 2022.05.23

Page 1 of 1



Performing Arts
Division –
Technical Support
Section

Sai Wan Ho Civic Centre
111 Shau Kei Wan Road
Sai Wan Ho, H.K.

Phone
852-2550 7155
Fax
852-2904 6297

Hall size	<i>Width</i>	12.86m
	<i>Depth</i>	17.65m
	<i>Height</i>	4.58m
	<i>Clear under truss</i>	3.86m

Seats	110 for end stage setting (movable seats)
	Or 100 for thrust stage setting (movable seats)

Stage Surface	Brown Surface Sprung Flooring
----------------------	-------------------------------

Flying System	None
----------------------	------

Intercom system	Single channel
------------------------	----------------

Wardrobe	None
-----------------	------

Dressing Rooms	1 room fitted with private toilet and shower for 10 persons
-----------------------	---

Electrics	ETC Ion Xe Control Console in lighting control room
------------------	---

Sound	Soundcraft Si Performer 1 Console; max. 6 mic/line channels to audio control room d&b E12 PA Speakers
--------------	--

Projection	Eiki EX-3500A – 16mm portable film projector Multi-media projector (SANYO PLC-XU106) (incur extra charges)
-------------------	--

Storage Space	None
----------------------	------

Get-in	By cargo lift , size : 5.38 x 2.40 x 1.90m(W x H x D)
---------------	---

Crossover	None
------------------	------

Equipment	Stage risers (Not suitable for dance program) Display panels
------------------	--

Other Facilities	Full-length mirrors with dancing bars
-------------------------	---------------------------------------

Instruments	Kawai upright piano (Only preset on stage floor)
--------------------	--

CONTACTS

Iris Lam
Senior Manager (HKE)
Direct Line
852- 2550 7883

Iris Lo
Manager (SWH)
Direct Line
852- 2550 8559
Fax Line
852- 2567 4041

Sunny Wong
Resident Technical
Manager (HK)
Direct Line
852-2853 0730 (SWCC) /
2550 7203 (SWHCC)
Fax Line
852- 2850 6250

GENERAL SET-UP

The Cultural Activities Hall operates on a 'bare-walls' touring policy. That is, all equipment is normally set-up and struck within the booking period. Hires are reminded to allow sufficient preparation time to hang theatre masking, rig all overhead stage lighting and set up sound system.

INFORMATION

Full technical drawings available